

Government of the Northwest Territories
Department of Lands
86 Duck Lake Road
Inuvik, NT
XOE-OT0

DOL Review and comments for Km 147

The application was reviewed and with reference to the QOP Spill Contingency Plan. Lands comments are in bold. Reviewers are aware this is on GTC private Lands and hope the comments will be of assistance in making their decision.

3 Sediment and Erosion Control Plan –Mitigation Monitoring

All sediment and erosion control measures will be monitored daily during construction by the contractor and INF personnel. This is to ensure the mitigation techniques employed are functioning and maintained properly. Mitigation measures that may not be working will be repaired or revised immediately.

The contractor and INF personnel will visually inspect the quarry on a daily basis for potential sources of sedimentation or erosion which may affect a nearby waterbody or watercourse. If sedimentation or erosion is occurring and sediment is entering a watercourse or waterbody, hourly turbidity by INF personnel will be conducted until the problem is rectified.

Inspector has no concerns with the plan and would like to inform that with the terms and conditions of the LUP weekly inspection to the sites will be planned to ensure mitigation will be followed and terms and conditions of the permit are adhered to.